35

BRUHAT BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARINAGAR ZONE
ELECTRICAL DIVISION
WORK ORDER SCHEDULE OF ITEMS WITH APPROVED RATES

Name of the Work: Providing 250 watt HPSV Street lights in Roads/layots of Ward no 40 in RR Nagar zone.

Sl. No	Description of Item	Unit	Qty	As per Sanctioned		Vaishnavi Enterprises	
				Rate	Amount	Rate	Amount
1	Wiring for lighting/power circduit using one of PVC insulated 1100v grade staranded **Aluminium** unsheathed wire single core/multi core cable in open or consealed system of wiring.						
	4 sqmm	Per Mtr.	112	9.50	1064.00	6.20	694.40
2	Supplying High pressure sodium uapour street ligh fitting **die cast aluminium conopy** with aluminum housing for cdontrol gear, finished stove enamel gray glassy white canopy interior with a pair of anodzed aluminum reflectors clear acrylic bowl, gasket lining for drip inseat resistance duly eited with porcrlain holder copper choke, igniter and HPF condenser including a sodium vbapour lamp.						
	II 250 Watts						
	Group 'A'	Each	28	6150.00	172200.00	4040.50	113134.00
3	Supplying & fixing...mm dia class A GI pipe bracket uup to 2.7 meters long for fixing MV/SV/MH/FTL street light fitting of all capacities on rail/ RCC/Wall/tubular pole, using suitable clamps, bolts and nuts and wiring using suitable capacity wires etc complete.						
	Using 32mm dia G.I. pipe	Each	30	885.00	26550.00	581.00	17430.00
	Total				**199814.00**		131258.40
Tender premium amount at 34.30% above Est Amt					**34.30**		
Total amount Admissible Rs							

For Vaishnavi Enterprises

Executive Engineer (Elec) 30/9/13
Rajarajeshwari Nagar Zone
Bruhat Bangalore Mahanagara Palike